UMTS Lighting Schedule	Quantity	Length	Brand	Fixture item #	Type	
RTIC Building						
Washbay	18	4'	Eiko	VPHB2-PS135-8FCCT-HDIM	Vapor Tight High Bay	
Bus Storage	66	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Parts Room	24	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Electrical Room	2	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Subtotal	110					110
UMass Transit Building						
Machine Shop	10	4'	LUXRITE	LR25363	Strip Light	
Back of parts room	8	4'	LUXRITE	LR25363	Strip Light	
Hallway outside parts	2	4'	LUXRITE	LR25363	Strip Light	
Custodial closet	1	4'	LUXRITE	LR25363	Strip Light	
Mezzanine	7	4'	LUXRITE	LR25363	Strip Light	
Boiler Room	3	4'	LUXRITE	LR25363	Strip Light	
Lower parts room	5	4'	ENVISION	LED-WRP-ARC-10ix4FT-3P50-5CCT	Wrap Light	
Restrooms	4	4'	ENVISION	LED-WRP-ARC-10ix4FT-3P50-5CCT	Wrap Light	
Superintendent Office	2	2'x2'	Warelight	WL-BLPLED-2x2-32W-5WS-5CCT-DM010-G2	Surface Mount Panel light PULL CHAIN	
Foreman Office	1	2'x4'	Warelight	WL-BLPLED-2x4-50W-5WS-5CCT-DM010	Suspended Ceiling Panel Light	
Cold Tank Room	1	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Tool Room	1	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Vanity Lights in Restrooms	2	2'	Warelight	WL-SWLED2-20W-CWS-WH	Vanity Light/ PULL CHAIN	
Compressor Room	1	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Bypass Lane	8	2'	Phillips/day-brite	fbx08LL40-UNV	High Bay	
Parts Room Stairwell	1	4'	LUXRITE	LR25363	Strip Light	
Subtotal	57					
Total	**167**					57